

S.NO.	PARTICULARS	NO.	L	B	H	QUANTITY	UNIT	RATE	AMOUNT
1	Excavation	1	315.50	0.45	0.90	127.78	cmt.		
2	Rubble Soling	1	315.50	0.45	0.20	28.40	cmt.		
3	P.C.C.	1	315.50	0.45	0.10	14.20	cmt.		
4	Masonry in Foundation	1	252.50	0.40	0.90	90.90	cmt.		
5	Backfilling					24.58	cmt.		
6	Masonry pillars	85	0.30	0.30	1.60	12.24	cmt.		
7	Kudchi Masonary wall	1	227.00		1.50	340.50	smt.		
8	P.C.C. Coping on wall	1	227.00	0.23	0.20	10.44	cmt.		
9	P.C.C. Coping on pillars	94	0.45	0.45	0.20	3.81	cmt.		
10	Excavation for Footings	2	1.20	1.20	1.00	2.88	cmt.		
11	Rubble soling for footings	2	1.20	1.20	0.20	0.58	cmt.		
12	P.C.C. For footings	2	1.20	1.20	0.10	0.29	cmt.		
13	RCC footing	2	1.00	1.00	0.45	0.90	cmt.		
14	RCC columns	2	0.30	0.30	1.80	0.32	cmt.		
15	Masonry in foundation	1	63.00	0.40	0.50	12.60	cmt.		
16	Exposed masonry in foundation	1	63.00	0.40	0.70	17.64	cmt.		
17	Exposed masonry pillars	18	0.30	0.30	1.60	2.59	cmt.		
18	Exposed masonry wall	1	57.00	0.23	0.90	11.80	cmt.		
19	Exposed stone coping for pillars	18	0.45	0.45	0.20	0.73	cmt.		
		2	0.50	0.50	0.45	0.23	cmt.		
20	Exposed stone coping for wall	1	57.00	0.30	0.15	2.57	cmt.		
21	Plaster	2	315.50		0.45	283.95	smt.		
		2	227.00		0.07	29.51	smt.		
		340	1.60		0.07	38.08	smt.		
		2	227.00		1.50	681.00	smt.		
		170	0.30		1.60	81.60	smt.		
		2	227.00		0.20	90.80	smt.		

		170	0.45	0.20	15.30	smt.
		8	0.30	1.80	4.32	smt.
		4	0.45	0.20	0.36	smt.
22	Laterite cladding for R.C.C. Columns	8	0.40	1.80	5.76	smt.
23	M.S. Powder coated designer Railing	19	3.00	0.75	42.75	smt.
24	M.S. Powder coated Gates (2 shutter)	2	4.20	3.50	29.40	smt.